

**CITY OF FERNDALE**  
**PS #2 & PS #3 Upgrades Project**  
**ADDENDUM NO. 4**

Issue Date: June 27, 2016

General: Recitations of each and every section of the bid documents impacted by this addendum are not given. The described changes impact all relevant portions of the bid documents whether specifically cited below or not.

**CLARIFICATIONS AND REVISIONS**

**DIVISION 16 – ELECTRICAL – General Clarifications**

Item #1: Section 16910.2.05: Clarification: Cooling fans shall be provided for ventilation in all VFD enclosures, as specified.

Item #2: Section 16925.2.3.B.5: Revise part number to #2711P-B7C4D8: PanelView Plus 6 Terminal, 700 Model, Keypad/Touch, Color, Standard Communication - Ethernet & RS-232, DC Input, Windows CE 6.0

Item #3: Section 16925.2.2.B.4: Clarification: MiniCAS seal fail and thermal relays and indicator lights are required for each pump in the system and shall be wired in each pump control circuit, as specified.

Item #4: Section 16925.2.2.C: Clarification: All items in this section shall be provided and wired in each individual pump control circuit including but not limited to: Individual control power transformers, voltage monitor, surge protector, CTs and ammeter with 3 position switch, and elapsed time meter/start counter.

Item#5: Section 16925.2.2.C.2: Backup Float Controls. Clarification: Pump call relays shall include time-on delay relays per Section 16925.2.2.C.1.m to stagger pump starts. High and Low floats wired to existing telemetry panel shall include latching relay circuit for additional redundancy.

\*\*\* END OF ADDENDUM #4\*\*\*

