



**Reichhardt & Ebe**  
ENGINEERING INC

TRANSMITTAL SHEET

Date sent: Friday, May 27, 2016

Sent to: All Planholders

Deliver to: Project Estimator

Transmission sent from: Reichhardt & Ebe Engineering

**CONFIRMATION OF RECEIPT OF ADDENDUM**

**PROJECT: CONSOLIDATION OF CENTRAL CITY WATER  
PROJECT #WA2015-01**

---

Please complete the following form and email back to Reichhardt & Ebe Engineering, Inc. at [officeadmin@recivil.com](mailto:officeadmin@recivil.com) as soon as possible.

Have you received Addendum No. 2 for the above-mentioned project?

**YES, we received Addendum No. 2**

Signed: \_\_\_\_\_ Dated: \_\_\_\_\_

Company name (Please Print): \_\_\_\_\_



**Reichhardt & Ebe**  
ENGINEERING INC

**TRANSMITTAL SHEET**

TO: ALL BIDDERS	FROM: Luis Ponce, P.E.
COMPANY:	DATE: May 27, 2016
ADDRESS:	TOTAL NO. OF PAGES INCLUDING COVER: 3

RE:  
City of Ferndale  
Addendum 2  
CONSOLIDATION OF CENTRAL CITY WATER PROJECT #WA2015-01

NOTES/COMMENTS:

**To the attention of all bidders for the above project:**

Please find the enclosed Addendum for the above referenced project.

The enclosed ADDENDUM is to be considered as much a part of the Contract Documents as if it were included in the body of the plans and specifications, and will be incorporated in and made a part of the contract when awarded and when formally executed.

The Bidder shall acknowledge in writing, on the bid form, this addendum in order to have the bid considered.

Luis Ponce, P.E.



5/27/16

**ADDENDUM NO. 2**  
**To the Contract Provisions for**  
**CITY OF FERNDAL, WASHINGTON**

**Consolidation of Central City Water Project #WA2015-01**

**ITEM 1**

**7-08.5 Payment**

Page 96, lines 39-47 are deleted.

**ITEM 2**

**7-09.3(8) Removal and Replacement of Unsuitable Materials**

Section 7-09.3(8) is supplemented with the following:

Quarry spalls shall be used to backfill the removed unsuitable foundation material.

**ITEM 3**

**7-09.4 Measurement**

Section 7-09.4 is supplemented with the following:

Removal of unsuitable foundation material will be measured by the cubic yard. The depth shall be the actual depth removed below the depth specified in Section 7-09.3(5) and as shown in the Plans. The width shall be the actual width removed, but in no case shall the measured width exceed the allowable widths specified in Section 7-09.3(7).

“Quarry Spalls” used for foundation material as shown on the Plans shall be measured per ton.

**ITEM 3**

**7-09.5 Payment**

Section 7-09.5 is supplemented with the following:

“Removal of Unsuitable Material Including Haul”, per cubic yard.

The unit contract price per cubic yard for “Removal of Unsuitable Material Including Haul” shall be full pay for all work to remove unsuitable foundation material, haul and disposal of unsuitable foundation material.

Payment for “Quarry Spalls” required for foundation material as shown on the Plans shall be per ton.